# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17859

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/01/2015-16**

**Improvements to Roads and Drains at Basavalingappanagar in Ward No.05, Byatarayanapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K NARASIMHA RAJU | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 679.00 | KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2014-15 | cum | 120.0 | 81480.00 | Rupees One Hundred Twenty Only |
| 2 | 3247.20 | Removing B.S Slab of Drain and stacking Page No.25/ Item No. 5.32/ PWD SR 2014-15 | Sqm | 50.0 | 162360.00 | Rupees Fifty Only |
| 3 | 3247.20 | Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2014-15 | Sqm | 70.0 | 227304.00 | Rupees Seventy Only |
| 4 | 811.80 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No.25/ Item No. 5.31.1/ PWD SR 2014-15 | Sqm | 600.0 | 487080.00 | Rupees Six Hundred Only |
| 5 | 1376.00 | KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406,P No. 154/ Item No. 20.18/ PWD SR 2014-15 | Cum | 1375.58 | 1892798.08 | Rupees One Thousand Three Hundred Seventy Five and Fifty Eight Paise Only |
| 6 | 7280.00 | KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5, No. 175/ Item No. 21.4/ PWD | Sqm | 30.0 | 218400.00 | Rupees Thirty Only |
| 7 | 182.00 | KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 174/ Item No. 21.20/ PWD SR 2014-15 | Cum | 8400.0 | 1528800.00 | Rupees Eight Thousand Four Hundred Only |
| 8 | 679.00 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km ( Page No.123, | Cum | 60.0 | 40740.00 | Rupees Sixty Only |
| | | | | | **4638962.08** | |

K. Narasimha Raju

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**

16/2/16